

# **PROJECT INFORMATION BROCHURE**

## **Presbyterian Road over Tributary to Keshequa Creek Culvert Replacement Project**

**PIN 4BNY.43**

**Town of Mount Morris  
Livingston County**



## **PROJECT OBJECTIVES**

The following objectives have been established for this project:

- Replace the existing culvert with a structure with a design life of 75 years
- Provide a structurally sound culvert with minimal maintenance for 30 to 50 years
- Stabilize the slopes around the culvert openings

## **PROJECT DESCRIPTION**

The existing culvert will be replaced along the current alignment with a 3-sided concrete culvert on cast-in-place spread footings keyed into the bedrock. The size of the proposed culvert will match that of the existing culvert with a 14 foot span and a 10 foot rise. The wingwalls will be protected by stone fill keyed into the bedrock. The stone fill will be keyed in across the creek at the inlet and outlet to protect the embankment and help slow the water velocity.

Construction of the new culvert and highway modifications will require closure of the road with use of an off-site detour for approximately 3 months.

## **PROJECT FACT SHEET**

<b>Project Location</b>	Presbyterian Road over Tributary to Keshequa Creek, Town of Mount Morris		
<b>Proposed Alternative</b>	3-Sided Precast Concrete Culvert		
<b>Roadway Widths</b>		<u>Existing</u>	<u>Proposed</u>
	Travel Lane	2 – 11 ft.	2 – 11 ft.
	Shoulder	2 – 2 ft.	2 – 4 ft. paved
<b>Structure Information</b>		<u>Existing</u>	<u>Proposed</u>
	Year Constructed	1927	2023
	Material	Concrete	Precast Concrete
	Type	3-Sided Frame	3-Sided Frame
<b>Additional Right-of-Way</b>	No right of way acquisitions are anticipated for this project		
<b>Environmental Classification</b>	State Environmental Quality Review Act – Type II (no significant impact).		
<b>Pedestrian Access</b>	Pedestrians will not be permitted in the project area during construction.		
<b>Maintenance of Traffic</b>	During construction, a temporary offsite detour will be used.		
<b>Anticipated Schedule</b>	Begin Construction – June 2023 End Construction – August 2023		
<b>Construction Cost</b>	Estimated at \$773,200 (The project is funded 100% State)		
<b>Contact Person</b>	Zac Cracknell - Livingston County Highway Dept. Project Manager Phone: (585) 243-6700 Email: <a href="mailto:ZCracknell@co.livingston.ny.us">ZCracknell@co.livingston.ny.us</a>		

